

the relevant provisions of Section 701 of the Standard Specifications and the following:

Cement concrete sidewalks at driveways will be paid for, complete in place, at the contract unit price per square yard, under Item 701., which price shall include all labor, materials, equipment and incidental cost required to complete the work to the satisfaction of the City of New Bedford or its authorized representative, including, but not limited to, sawcutting existing pavement and sidewalks, gravel borrow, fine grading and compacting, and the disposal of any excavated materials.

<u>ITEM 701.2</u>	<u>CEMENT CONCRETE WHEELCHAIR RAMPS</u>	<u>SQUARE YARD</u>
-------------------	---	--------------------

The work to be done under this item consists of installing new cement concrete wheelchair ramps within the limits of work as shown on the plans. All work shall be in accordance with the relevant provisions of Section 701 of the Standard Specifications and the following:
The wheelchair ramps shown on the plans are a graphical representation of the ramps. The Contractor shall determine the appropriate transition lengths in accordance with AAB and ADA wheelchair ramp standards.

Cement concrete wheelchair ramps will be paid for, complete in place, at the contract unit price per square yard, under Item 701.2, which price shall include all labor, materials, equipment and incidental cost required to complete the work to the satisfaction of the City of New Bedford or its authorized representative, including, but not limited to, sawcutting existing pavement and sidewalks, gravel borrow, fine grading and compacting, and the disposal of any excavated materials.

<u>ITEM 804.3</u>	<u>3 INCH ELECTRICAL CONDUIT</u> <u>TYPE NM - PLASTIC (UL)</u>	<u>FOOT</u>
-------------------	---	-------------

The work under this item shall conform to the relevant provisions of Section 800 of the Standard Specifications and the following:

The work shall include furnishing and installing 3 inch, non-metallic plastic conduit, for traffic signal systems in accordance with the plans and as required by the City of New Bedford or its authorized representative. The conduit material shall be Schedule 40 polyvinyl chloride (PVC) plastic conduit. The length of conduit may be increased or decreased by the City of New Bedford or its authorized representative depending upon actual conditions encountered as provided for in Section 4.06 (Division I) of the Standard Specifications.

Conduit in grass or in planted areas

Where new conduits are installed in grass and planted areas, work shall include placement of a minimum of 6-inches of loam borrow, seed, and any other materials replaced in kind to restore disturbed areas to their original condition. Any existing plants (bushes, flowers, etc.) removed or damaged as a result of this project shall be replaced in kind. No separate payment shall be made for this work, but all costs in connection therewith shall be included in the price for Item 804.3.