

Fluorescent Orange Reflectorized Sheeting
Minimum Coefficient of Retroreflection Ra
(Candelas per lux per 10.76 square feet)

<i>Observation Angle</i>	<i>Entrance Angle</i>	
	-4°	30°
0.2°	180	100

Steady or flashing lights shall be used on Reflectorized Drums only at the direction of the City of New Bedford or its authorized representative and will be considered incidental to this item with no additional compensation.

ITEM 874.2

TRAFFIC SIGN REMOVED AND RESET

EACH

The work to be done under this Item shall include the dismantling, removal, transporting and resetting of the existing signs at the location indicated on the plans. The work also includes the removal and disposal of the existing sign supports and foundations.

The Contractor shall exercise particular care in the dismantling, removal, transporting and resetting of the existing signs designated to be reused. Any sign panel damaged through carelessness or lack of protection by the Contractor shall be replaced at the Contractor's expense.

Payment for new supports for signs to be removed and reset shall be included under Item 847.1. The Contractor shall backfill with compacted gravel all holes resulting from the removal of the existing signs and their foundations and restore the area to match existing conditions of adjacent areas.

The existing signs shall not be removed and reset without the prior permission of the City of New Bedford or its authorized representative.

Payment for removing and resetting signs will be at the respective Contract unit price Each and will be full compensation for dismantling, loading, transporting and resetting of the signs as designated above, the excavation, removal and disposal of their supports, and foundations, and the gravel backfill.

ITEM 874.4

TRAFFIC SIGN REMOVED AND STACKED

EACH

Work under this Item shall include the dismantling, removal, transporting and discarding of the existing roadside traffic signs and street signs as required by the City of New Bedford or its authorized representative including the removal and disposal of the sign supports and their foundations.

The work shall include removing the supports, excavating the existing foundation, the disposal of