

the concrete and supports, the backfilling with compacted gravel of the holes resulting from the excavation and removal of the supports and the replacement, in kind, of any surface material disturbed. The existing signs shall not be removed until the new signs and structures replacing them are ready for installation or until the City of New Bedford or its authorized representative orders their removal. Payment for work to be done under Item 874.41 will be at the lump sum contract unit price, which price will be full compensation for dismantling, loading, transporting, and stacking the signs and supports as designated above, the excavation and disposal of the existing foundations, the supplying and placing of compacted gravel backfill where foundations and posts are removed, restoration of surface, and all other incidentals necessary for the proper completion of this Item.