



PERMIT ONLY

extenetSM
SYSTEMS
YOUR NETWORK.
EVERYWHERE.

3030 Warrenville Road
Suite 340, Lisle, IL 60532

Project #: NE-MA-NEWBED-MPS

Job Title: New Bedford, Ma

Engineer: Scott McGee

Original Issue Date

Published Date: 3/11/09

Bill of Materials:

Description	Qty.
Fiber - 576	0
Fiber - 288	0
Fiber - 144	0
Fiber - 96	0
Fiber - 72	0
Fiber - 48	0
Fiber - 36	0
Fiber - 24	1,563'
Fiber - 12	0
Fiber - Drop	0
Total Fiber	1,563'
Route - Aerial	1,263'
Route - UG-Leased	0
Route - UG-New Conduit	0
Route - Base Station	0
Total Route Footage	1,263'
Poles - Power	11
Poles - Telco	0
Poles - Other	0
Total Poles	11
Nodes	0
1/4" Strand	1,263'
Anchor	1
Connector Splices	
Slack Loops	2
Handholes	0
Manholes	0

⊗ = JOINT POLE	⊗ = SLACK LOOP
× = POWER POLE	⊗ = ANCHOR
⊗ = NODE POLE	⊗ = GROUND
⊗ = SPLICE	⊗ = MANHOLE
⊗ = BRANCH SPLICE	⊗ = HANDHOLE
⊗ = STRAIGHT SPLICE	⊗ = VAULT
⊗ = BALLOON SPLICE	⊗ = PEDESTAL
⊗ = CONNECTING SPLICE	

Gabe's

4804 North 40th Street
Sheboygan, WI 53083
Phone: (920) 459-2600

MAP 32	MAP 31	
	MAP 30	

Map Number: MAP 31

Date	Description	Initials	Date	Description	Initials	Date	Description	Initials
6/2/08	NODE LOCATIONS	JO	2/2/09	REVISED DWGS	DMH			
6/17/08	NODE LOC OPTIONS	LO						
8/26/08	ROUTE REVISIONS	DMH						

State: MASSACHUSETTS
County: BRISTOL

Municipality: NEW BEDFORD
Township:

Scale: 1" = 200'