

For DISTURBANCE PERMIT within the City of New Bedford

APPLICATION / AGREEMENT

Date Issued:

June 24, 2021

Dig Safe #

Permit #

231-2021

This permit shall be posted at the work site, and shall remain until the work is completed. It is subject to inspection at all times.

TO THE MAYOR AND CITY COUNCIL:

☒ DISTURBANCE PERMIT

Permission is hereby requested to excavate the surface of: 1 City Property

45 Nash Road

P. 105

2.103

Location of work:

Nash Rd ex Hops St

Substantially as per plan annexed, for the purpose of: driveway

Duct 11630

Work will begin (weather permitting) on: 7-6-2021

Work will end (weather permitting) on: 10-6-2021

Applicant Name:

Nelson Cardoso

Excavator(s) Name:

Cardoso Contracting

Company Name:

Nelson Cardoso

Contact Name:

Title:

Project Manager

Approved By: Nelson Cardoso

Date: 7/7/2021

Provide Sketch

Name & Contact Number of Insurer: AP Insurance Group 508-992-3130

Grade:

Expiration Date:

Hoisting Equipment License Number:

Roadway closures will require authorization from the Commissioner of Public Infrastructure.
Traffic management plans may be required.
For inspection, 24-hour notice is required and the contractor/Applicant is required to
notify the DPW @ 508-979-1350. Press & Repair. Permit Expires in 3 Months from work start date.

LOT 42
N/F CLUB MADEIRENSE

HOPE

LOT 105
N/F TEIXEIRA

LOT 107
N/F TEIXEIRA

THE 6" GDR 35 PVC DRAIN
PROP. INV. = 14.50' - 9"
15' S.D. INV. = 14.10'

New Wheelchair Ramp

LOT 108
N/F D. LOPEZ

#43

Erosion Control Barrier

BENCHMARK: CATCH BASIN RIM
ELEV. = 20.00' (6' 11")

Erosion Control Barrier
Remove Concrete Apron To Edge Of Sidewalk
Cap/Cod/Berm On This Side

(6) Fence 80' 00"

Back Storage Area

24' x 48' Chain Link Fence
On 18" Masonry Wall
Solar Light Pole - Typ. for 2
Sprinkler @ 4' 8" o.c. - Total = 18

LOT 165
N/F DEMELO

PROPOSED 2' WIDE CRUSHED
STONE FILTER STRIP

HOUSE
59 NASH ROAD

6" PERF. 5DR 35 PVC
INV. = 16.60'

PROPOSED RAIN GARDEN

Erosion Control Barrier

New Tree - Typical For 4 (Note 6)

ASPHALT SIDEWALK

12' 6"

5DMH

15' S.D.

4" Grass Ribbon

New 5.5' Concrete
Sidewalk

Install 16' Granite Curb

NASH ROAD

4" D. YARD DRAIN RIM = 19.35'
6" UNDERDRAIN INV. = 16.60'

New Wheelchair Ramp

HOUSE
56 NASH ROAD

LOT 103
6,920 S.F.

Bituminous Pavement
(4,337 S.F.)

6 Spaces = 63'

Clean-Out @ Grade

NEW CONC. SIDEWALK

74.48'

CROSSWALK

(6) Granite Curb

GRASSY WALK

5DMH

15' S.D.