

Inspector:
Wednesday:
12:30/1:00 PM

Permit #	444-2021
Dig Safe #	20213913886
Date Issued:	October 01, 2021

APPLICATION / AGREEMENT
For DISTURBANCE PERMIT within the City of New Bedford

This permit shall be posted at the work site, and shall remain until the work is completed. It is subject to inspection at all times.

TO THE MAYOR AND CITY COUNCIL: / DISTURBANCE PERMIT

Permission is hereby requested to excavate the surface of: / City Property

Location of work: 421- 423 Belleville Avenue

Service #15790

Substantially as per plan annexed, for the purpose of: Install new copper water service - house to curb stop

Curb stop to Meter:

Work will begin (weather permitting) on: 10-5-2021

Work will end (weather permitting) on: 1-5-2022

Applicant Name: Eric Smith

Excavator(s) Name: W.C. Smith and Son

Company Name: W.C. Smith & Son, Inc.

Hoisting Equipment License Number: HE-039059

Grade: 2A Expiration Date: 12-13-2022

Contact Name: Eric Smith

Name & Contact Number of Insurer: Eastern Insurance

Approved By: Dorinda M. Amadio Date: 10/4/2021

Title: Admin Manager

Roadway closures will require authorization from the Commissioner of Public Infrastructure.

Traffic management plans may be required.

For inspection, 24-hour notice is required and the contractor / Applicant is required to

notify the D.P.I. @ 508-979-1550 Press 4 Repair. Permit Expires in 3 Months from work start date.

Provide Sketch

APPLICATION No., 15790 5/8" H lead

LOCATION: 421-423 Belleville Ave.

OWNER: Manuel Baptiste

MEASURES: ~~5/8"~~ 1"

S from
E from W line
S from N line

H lead
Phillips Ave.
Belleville Ave.
Bldg.

June 9, 1914
105.0 ft.
~~10.0 ft.~~
~~11.0 ft.~~

TAP CLEARED

DATE _____

BEF.

AFT.

REMARKS

8/6/71

Reamed

6/1/83

Reamed

August 6, 1971 Renewed from the main to a point 6"
inside curb stop

9½ ft. - 3/4" Copper tubing 3/4" Hays curb stop
3/4" x 3/4" Fig. 413 1 lb. wiping solder

June 1, 1983 Belleville Ave. Interceptor Sewer:
Renewed from the main to the property line.
22 ft. - 3/4" Copper tubing 1 - 5/8" x 3/4 Fig. 413
1 - 3/4" Curb stop Caldwell Stop Box
1 5/8" x 3/4" lead to copper adapt XXS

Measures of new curb stop:

E x W line Belleville Ave. 9.5 ft.

S x N line Bldg. 4.0 ft.

Measures of 1" Corp. Tap.

S x S Line Phillips Ave. 102.6 Ft.

E x W Line Belleville Ave. 33.0 Ft.

August 18, 1976 - Zoppo Const. installed a 1" tap during the installation of 48" main.