Permit #	108	-20	23
. C	100	0.0	~

Dig Safe # 20230704326

Date Issued: February 21, 2023

## APPLICATION / AGREEMENT

For DISTURBANCE PERMIT within the City of New Bedford

This permit shall be posted at the work site, and shall remain until the work is completed. It is subject to inspection at all times.			
TO THE MAYOR AND CITY COUNCIL: DISTURBANCE PERMIT			
Permission is herby requested to excavate the surface of: City Property			
Location of work: 121 North Street			
Substantially as per plan annexed, for the purpose of: Installing electrical conduit			
Work will begin (weather permitting) on: $2 - 27 - 23$			
Work will end (weather permitting) on: 5-27-23			
Applicant Name: Kirk Franklin	Excavator(s) Name: Kirk Franklin		
Company Name: Frank Corp. Environmental Services	Hoisting Equipment License Number: $\underline{HE-076597}$ Grade: $\underline{2A}$ Expiration Date: $\underline{9-6-24}$		
Contact Name: Kevin Rocha	Name & Contact Number of Insurer: Smithwick & Mariners 207-791-5553		
Approved By: Annam. Ameda Date: 2/24	1		
Title: Jamin manager	Provide Sketch		
Roadway closures will require authorization from the Commissioner of Public Infrastructure.  Traffic management plans may be required.	attached		
For inspection, 24 hour notice is required and the Contractor / Applicant is required to notify the D.P.I. @ 508-979-1550 Press 4 Repair. Permit Expires in 3 Months from work start date.			

EVELOUILE EILEIGY Auth. No. Work Order Number: Page Number: City: ervice Address: NEW BEDFORD 11715495 121 NORTH ST Date Prepared by: istomer's Name/Title: JOSEPH PASTERIS 31JAN23 HOLY FAMILY LLC 2-89-14 ales Representative: JANET COSTA Circuit Number: **NEW UG SVC** 290579 (58% LOADED) MATTHEW CABUCIO (774) 226-3026 ectrician: N/A Secondary Sheet Number: vitch Size: AT MH8000/385-SUMMER **EVERSOURCE WORK-**INSTALL HH8000/385A (FE2A) AT INDICATED PROPOSED LOCATION LOT 1 INSTALL 4" STUB DUCT AT HH (5' +/-) TOWARD CUSTOMER SERVICE POINT AC PAD INSTALL ONE 4" CONDUIT BETWEEN MH8000/385 & HH8000/385A (25' + /-)PROPOSED USE: INSTALL TWO 500MCM CU HOT LEGS MURTI-FAMILY RESIDENCE AND ONE 4/0CU NEUTRAL CONDUCTOR (15 UNITS) BETWEEN MH 8000/385 & HH8000/385A (25' +/-) MAKE CONNECTIONS IN MH 8000/385 & SERVICE CONNECTIONS TO NEW CUSTOMER SERVICE CABLE IN HH8000/385A HOLY FAMILY SCHOOL/CHURCH SECONDARY HH HH8000/385A 1249 +/- 25' 0 CUSTOMER WORK-→ MH 321 MH 385 **INSTALL SERVICE CONDUIT & SERVICE** NORTH STREET ~PUBLIC - 40' WIDE~ CABLE BETWEEN HH8000/385A AND BUILDING #121 (LEAVE ENOUGH SLACK FOR

EVERSOURCE TO MAKE SERVICE CONNECTIONS IN HH8000/385A)