



PERMIT NO.

23903-EXT.

CITY OF NEW BEDFORD
SEWER AND/OR STORM DRAIN PERMIT

DATE 10/26/06

This certifies that permission is granted to

John Carriga 291 Middle St. Fall River 508.677.9234
Property Owner Address Tel.

To connect a sewer and/or storm drain located at Hathaway Rd. Gravity on west part of A.T. La
Assessor's Plot 120 Lot 2, to the sewer and/or storm drain in Apple Tree Lane Street

To be laid in accordance with the conditions in this application and the City of New Bedford ordinances.

TYPE OF USE: ☒ RESIDENTIAL ☐ COMMERCIAL ☐ INDUSTRIAL ☐ OTHER

If applicant other than actual property owner, attach Letter of Authorization from Property Owner.

Name J.B. Lanagan - Steve R. Mendes Tel. 508.984.1668

Mailing Address 21 East River Dr. Dartmouth

The Bonded Contractor/Drain Layer authorized to perform this work is:

J.B. Lanagan 21 East River Dr. Dartmouth 508.984.1668

Name Address Tel.

Type of Pipe Required: SDR 35 PVC

Plan states 4" force main + house connections

PERMIT EXPIRES ONE YEAR AFTER DATE OF ISSUE

- Requires separate connections for sewage and storm drain where applicable. Storm water cannot be discharged to a sanitary sewer.
 - All work must be inspected and approved by a D.P.I. inspector before backfilling.
 - If this connection is to be part of a private service shared jointly with other building owners, attach copy of Recorded Joint Maintenance Agreement.
 - Permits can be issued to Industrial and/or Commercial Applicants only upon receipt and approval by the Commissioner of Public Infrastructure of required plans and supplemental information.
 - In addition, a City-issued Industrial User Discharge Permit and/or a Sewer Extension/Connection Permit issued by the Commonwealth of Massachusetts D.E.P. shall be required by the City for Industrial Discharge into the sewer system.
- Industrial User Discharge Permit No. Date

Comm. Mass. Sewer Conn./Ext. Permit No. W.07.14685 Date

A Filing and Inspection Fee of \$150.00 plus an Entrance Fee of \$75.48 where applicable, must accompany this application.

Bank# Sovereign Check# 17107 Date 10/23/06 Receipt# 6181

Other requirements: 24 hr inspection notice at 508.979.1527

Connection made to ☒ Sewer ☐ Storm Drain Part of jointly-shared private line YES ☒ NO

Applicant agrees to abide by the above terms, as well as all pertinent ordinances of the City of New Bedford, and such other special rules as the Commissioner of Public Infrastructure and/or City Engineer may deem necessary

Duarte M. Andrade Acting City Engineer mn


Signature of Property Owner or Representative

INSPECTOR'S REPORT

INSPECTED BY: DATE: COMMENTS:

APPROVED DISAPPROVED

SIGNATURE



SKETCH PLAN



PERMIT NO.

23903 - EXT

CITY OF NEW BEDFORD
SEWER AND/OR STORM DRAIN PERMIT

DATE 10/20/06

This certifies that permission is granted to

John Carrigg 291 Middle St. Fall River 508 677 9234
Property Owner Address Tel.To connect a sewer and/or storm drain located at Hathaway Rd. Force Main on east part of A.T.L.
Assessor's Plot 120 Lot 2, to the sewer and/or storm drain in Winterberry Terr. and Apple Tree Lane Street

To be laid in accordance with the conditions in this application and the City of New Bedford ordinances.

TYPE OF USE: ☒ RESIDENTIAL ☐ COMMERCIAL ☐ INDUSTRIAL ☐ OTHER

If applicant other than actual property owner, attach Letter of Authorization from Property Owner.

Name J.B. Lanagan - Steve Rzezendes Tel. 508 984 1668

Mailing Address 21 East River Dr. Dartmouth

The Bonded Contractor/Drain Layer authorized to perform this work is:

J.B. Lanagan 21 East River Dr. Dartmouth 508 984 1668
Name Address Tel.

Type of Pipe Required: SDR 35 PVC

Plan states 4" force main + house connections

PERMIT EXPIRES ONE YEAR AFTER DATE OF ISSUE

- Requires separate connections for sewage and storm drain where applicable. Storm water cannot be discharged to a sanitary sewer.
 - All work must be inspected and approved by a D.P.I. inspector before backfilling.
 - If this connection is to be part of a private service shared jointly with other building owners, attach copy of Recorded Joint Maintenance Agreement.
 - Permits can be issued to Industrial and/or Commercial Applicants only upon receipt and approval by the Commissioner of Public Infrastructure of required plans and supplemental information.
 - In addition, a City-issued Industrial User Discharge Permit and/or a Sewer Extension/Connection Permit issued by the Commonwealth of Massachusetts D.E.P. shall be required by the City for Industrial Discharge into the sewer system.
- Industrial User Discharge Permit No. _____ Date _____

Comm. Mass. Sewer Conn./Ext. Permit No. W074685 Date _____

A Filing and Inspection Fee of \$150.00 plus an Entrance Fee of \$75.00 where applicable, must accompany this application.

Bank# Sovereign Check# 17107 Date 10/23/06 Receipt# 6181

Other requirements: 24 hr inspection notice at 508 979 1527

Connection made to ☒ Sewer ☐ Storm Drain Part of jointly-shared private line YES ☒ NO

Applicant agrees to abide by the above terms, as well as all pertinent ordinances of the City of New Bedford, and such other special rules as the Commissioner of Public Infrastructure and/or City Engineer may deem necessary

Duarte M. Andrade
Acting City Engineer mn

Signature of Property Owner or Representative


INSPECTOR'S REPORT

INSPECTED BY: _____
DATE: _____
COMMENTS: _____

APPROVED

DISAPPROVED

SIGNATURE



SKETCH PLAN



**CITY OF NEW BEDFORD
MASSACHUSETTS**

D.P.L. -Engineering Division

1105 Shawmut Ave.

New Bedford, Ma. 02746

Tel: 508-991-6150

Fax: 508-961-3054 791-6152

Ronald Labelle
Commissioner

Duarte M. Andrade,
Acting City Engineer

To Whom It May Concern:

I, JOHN CARRIGG, 291 Middle St Fall River, being
(Name) (Mailing Address)

Owner of property located at NEW BEDFORD MASS
80 Hill St Apt 3 834 Hathaway St

(X) Plot 120, Lot 2, hereby agree to allow J. B. LANAGAN & Co., Inc.
(Name)

21 East River Dr., N. DARTMOUTH MA to act on my behalf including affixing my
(Mailing Address)

signature in securing permit for:

☒ Sewer/Drain Service Permits
☒ Water Service Permits
☒ Driveway Installation Permits
☒ Sidewalk Installation Permits

I further agree to conform to, and abide by, All City rules and ask regulations applicable to the permit (s) being applied for:

Name [Signature]
Signature

291 Middle St Fall River, MA 02724
Address

10-20-06 508-677-9237
Date Telephone Number

10/24/06 Gave to J. B. Laragan Co.

Permit No. W074685
NEW BEDFORD

**DEPARTMENT OF ENVIRONMENTAL PROTECTION
DIVISION OF WATER POLLUTION CONTROL**

The following special conditions apply to the sewer extension permitted hereunder:

1. Sewer line and water main separation shall conform to guidelines in TR-16, Guides for the Design of Wastewater Treatment Works, 1998 Edition. Conformance includes placement of the water line above the sewer line with a vertical separation of 18 inches from top of sewer to bottom of water line. If this separation requirement cannot be met, then both water main and sewer line shall be constructed of mechanical joint cement-lined ductile iron pipe for a distance of 10 feet on each side of the crossing with a full length of water line centered over the sewer. Both pipes should be pressure tested to 150 psi to ensure they are watertight and both pipes shall be structurally sound.
2. All gravity sewer piping material shall be a minimum of ASTM D3034 SDR 35 PVC pipe.
3. Drop type manholes shall be provided for sewers entering manholes with elevations of twenty-four (24) inches or more above the manhole invert.
4. The permittee shall construct the pump station in accordance with the City of New Bedford, Massachusetts specifications and shall be responsible for ownership, operation and maintenance, including an operation and maintenance agreement with a service company, until the City of New Bedford, Massachusetts assumes ownership and operation responsibilities.
5. Provide appropriately sized thrust blocks or appropriate mechanical restraints at all changes in direction of the force main.
6. In addition to details and information shown on the submitted plans, the on-site pump station shall also include all of the following:
 - a. automatic alternation of the lead/lag pump;
 - b. an alarm for loss of power;
 - c. telemetry for all alarms to signal at a facility manned 24 hours per day or to an automatic dialer system;
 - d. ventilation for the wet well.

END OF SPECIAL CONDITIONS