
SERVICE 34125

31-727

NEW BEDFORD WATER WORKS ,

SERVICE	34125	APPLICATION	FOR	SERVICE	AND	METER	
Sewer 249:	36	NEW BED	FORDO	18.2021 d	ku 051	3.2022	
I HEREBY ACK	NOWLEDGE the re	eceipt of a copy of the Re	gulations	prescribed in	the Ordina	nce of the	
City, for the use	of Water, and I	request that the water r	may be fi	urnished throu	gh a		
i	nch Copper	meter at A	my St	SS.) 240' L) XACUST	net Ave	
Plot 134 Lot	123						
		o time be established by					
I hereby agree t	o pay promptly th	ne bill for the Service pi	pe laid d	own for my pr	remises, a	nd to pay	
all dues for wat	er, and I agree to	conform to the said Reg	ulations	and to all prov	risions of t	he Water	
0	il written notice is	s given by me or my ag				1 - 2-0	
rgle tamily		HOW	rio l'iaru	inho, 90 Bric	yes, tai	shaven, many	
	TEI EDI	HONE 714-263-1105	* See a	ttached fo	۷.		٠
			" (
Service laid K	unessa	Size and kind of pi	pe l	PSER	• • • • • • • • • • • • • • • • • • • •		
From 8 ma	no (A) on	Almy St				St.	
Turned on						······	
Reading		Location	•••••				
Building rates	50		Paid				
Cost of Service 5	X		Paid C	rock # 2700	4		
Od Mom							



Commonwealth of Massachusetts



City Hall, Room 308, 133 William Street New Bedford, MA 02740 (508) 979-1540

3/2/2021

No. B-20-785

MSBC Sect. 111.8 - Any permit issued shall be deemed abandoned and invalid unless the work authorized by it shall have been commeced within six (6) months after its issuance.

FEE PAID \$100.00

This certifies that Seth Desroches		
owner/contractor has permission to:	SS- ALMY ST	
on:	134- 124	
Foundations Only 1-2 Family - 100.00		
Providing that the person accepting this permit shall in every of the statute of the Comonwealth adn to the by-laws of the Creparing, or tearing down of a building. Permit is issued subject to the fo	respect confrom to the terms of application city of New Bedford relating to the inspection llowing special requirements: (Restrictions)	therefore on file in this office; to the provisions , erection, enlarging, altering, raising, moving,
Wiring Inspector	Plumbing Inspector	Building Inspector
YOUR AREA INSPECTOR IS: Mattle	hew Silva	Tel. (508) 979-1540 Between 8:00am - 9:00am
1001(711(2)71116) 20.000		Tel. (300) 979-1340 Detween 8.00am - 9.00am
NOTICE: NOTIFY INSPECTOR 48 HOURS IN ADVANCE OF APPLYING SHEATHING OR LATH	No Building of Chrysture shall be used as assessi	REQUIRED BEFORE OCCUPANCY ed until the Certificate of Use and Occupancy shall have been issued 0.1
This Card Must Be Displayed in a Conspicuous	Place on the Premises and Not Torn Down or	Removed Until Completion of Work

SUBJECT TO MASSACHUSETTS STATE BUILDING CODE Dany D. Romonowery x

Plan Review Comments:

: 780 CMR 110.5 Inspection Requests - It shall be the duty of the holder of the building permit or their duly authorized agent to notify the building official when work is ready for inspection. It shall be the duty of the permit holder to provide access to and means for inspections of such work that are required by 780 CMR. The building official may require the permit holder or his or her representative to attend these inspections.

: Scope of Work

Install a foundation for a single family dwelling raised ranch

- -16"x12" footing with key way
- -8" concrete foundation
- -2" ridge insulation on the interior concrete wall.
- -3-1/2" concrete slab for the house to sit on top of compacted crushed stone, and 6 mil vapor barrier.
- -Foundation insulation shall be installed in accordance with the 2015 IECC.
- : Sewer & water permits must be applied for with DPI before the building permit is issued. As-built for the new foundation must be submitted to Inspectional Services before building permit is issued
- : THIS FOUNDATION WILL REQUIRE AN ELECTRICAL PERMIT FOR A "UFER GROUND" CONCRETE ENCASED ELECTRODE FOR CONNECTION TO THE BUILDING GROUNDING ELECTRODE SYSTEM PER THE NATIONAL ELECTRICAL CODE ARTICLE 250.52(3).
- : 1. Sewer service to be 10 ft away from water service.
- 2. Water curb stop (shut -off) to be 1.5ft from face of curb/pavement.
- 3. Install water meter at point of entry to building
- 4. Owner to apply for water and sewer permits.
- : Any changes, alterations, removal, or installation of any plumbing or gas fixture will require a permit
- : PLease adhere to DPI Comments relative to Map/Lot
- : Construct a 48' x 36' foundation for a single family dwelling .

: ASR-DPI Engrg.

RE: TB-20-785 Almy St. (S.S.) 240' W. x Acushnet Ave. Plot 134 Lot 123 Reviewed 10/7/2020

PLEASE NOTE:

It is the responsibility of the applicant and the contractors to be familiar with DPI procedures/ regulations and ascertain that all proposed work which falls under DPI jurisdiction, whether shown on the submitted site plan or not, is identified and executed in accordance with City of New Bedford DPI Construction Standards/Specifications. The Certificate of Occupancy (CO) will not be signed for any work performed that is non-compliant and/or if any of the following conditions are not met.

The following conditions are to be met by the applicant (being the owner and/or their representative) as part of this permit approval:

- 1.) The revised site plan submitted via e-mail by John J. Romanelli (which has been uploaded by DPI into the View Permit system under Engineering) titled: "Building Permit Plan, Assessors Map 134 Lot 123 Almy Street, New Bedford, Massachusetts", having a date of 3/26/2020 (last revised date of 10/5/2020), as prepared by Zenith Consulting Engineers, LLC and stamped/signed by Jamie L. Bissonnette, P.E. (Civil), was approved as the "final" site plan and conditionally approved by DPI, as follows:
- a. Compliance with the City of New Bedford Stormwater Rules & Regulations/Ordinances is required for all project sites, regardless of size. All sites must implement sediment and erosion control measures and will be subject to the required construction site and sediment control inspections. Any project that involves disturbing 1 or more acres will require an EPA NPDES Construction General Permit (refer to Section 3.1.C of the Stormwater Rules & Regulations).
- b. The applicant is responsible for ensuring that Inspectional Services is provided with the "final" site plan (or any modifications approved by DPI thereafter) to be placed on file in the View Permit system.
- 2.) Must provide 1 stamped/signed copies of the "final" site plan approved by DPI for each of the permits being sought (i.e. water, sewer/drain and sidewalk/driveway permits) for the proposed structure. In addition, a copy of the foundation permit and of the stamped/signed foundation as-built plan must also be submitted.

Please Note: Any representative pulling permits on behalf of the owner must provide DPI with a permission slip. If the property was acquired within the past 6 months, then a copy of the recorded deed showing property ownership must also be provided.

3.) Must contact DPI-Engineering to measure for an address number once the front door is framed. The CO will not be signed unless the legal address issued by the City is permanently affixed to, above, or next to, the main door entrance to which it was assigned such that it is highly visible from the street.

Please be advised that any and all future modifications to the site plan that was reviewed/approved for the above project and placed on file at DPI as the "final" site plan must be resubmitted for review/approval if said changes entail work that falls under the jurisdiction of DPI.

: ASR-DPI Engrg.

RE: TB-20-785 Almy St. (S.S.) 240' W. x Acushnet Ave. Plot 134 Lot 123 Reviewed 5/15/2020

The site plan submitted via view permit for the above location was reviewed and found to lack the information required for DPI to conduct a proper review of the site. A revised site plan must be submitted for review and all proposed work must meet DPI requirements and construction specifications/standards. Copies are available through the DPI office.

The following is a quick checklist of the elements that need to be incorporated into all site plans submitted for review by DPI:

- 1. Please check that all existing site conditions are shown (i.e. abutting right-of-ways, driveways/sidewalks, curb/berm or edge of pavement, buildings, utilities, mains/service connections, shut offs, clean outs, septic system (if any), easements, grading, etc.). Make sure everything is properly called out/labeled (i.e. size/type of existing mains, services, type of curb/berm, etc.).
- 2. Show all proposed work (i.e. new structure(s), water/sewer/storm drain mains/service connections or septic system, driveway(s)-new/closure/widening, storm recharge system for roof runoff (to include calculations), details and grading, etc.). Make sure everything is properly called out/labeled (i.e. proposed 1" copper water service, proposed 18' wide asphalt driveway apron, etc.).
- 3. Based on the recorded ANR submitted in View Permit and the property information on file for this location, the building that is to be razed is not a dwelling, it is an accessory building (garage). The footprint is also larger on the site plan, but it appears it's due to the open porch that extends out the back side of the garage. Please update accordingly.
- 4. Check that the site plan being submitted has been stamped/signed by the proper professional(s) responsible for the site development and design (i.e. Professional Engineer and/or Land Surveyor, depending on the case). This plan must also be stamped by the Engineer who designed the infiltration system and the proposed utility connections.
- 5. Check with DPI to obtain the record information for the existing water/sewer within the ROW and update accordingly. Please make sure to inquire whether there was a sewer betterment and if a sewer service stub was left at the property line at the request of the owner for possible future development. Please check the required distances for placement of the water curb stop and sewer cleanout. Please update accordingly.
- 6. Please note that being that the garage shown on Lot 125 of the ANR plan is going to be razed, the subject lot (shown as Lot 1 on the ANR) will be assigned a parcel id of Map 134, Lot 123. Please update accordingly. The Lot 2 will be assigned Map 134, Lot 126, which is what it is already being called out as on the site plan submitted.

The design engineer and/or land surveyor should contact Engineering with any questions regarding the above comments and/or DPI requirements/construction specifications and standards that need to be met.

: The final site plan uploaded into View Permit as part of Engineering's (DPI) review dated 10/7/2020 appears to have gone missing from View Permit. I am reloading it today, 4/9/2021, so it stays part of the record.

ASR-DPI Engrg.

RE:

TB-20-785

Almy St. (S.S.) 240' W. x Acushnet Ave.

Plot 134 Lot 123

Reviewed 10/7/2020

PLEASE NOTE:

It is the responsibility of the applicant and the contractors to be familiar with DPI procedures/

regulations and ascertain that all proposed work which falls under DPI jurisdiction, whether shown on the submitted site plan or not, is identified and executed in accordance with City of New Bedford DPI Construction Standards/Specifications. The Certificate of Occupancy (CO) will not be signed for any work performed that is non-compliant and/or if any of the following conditions are not met.

The following conditions are to be met by the applicant (being the owner and/or their representative) as part of this permit approval:

- 1.) The revised site plan submitted via e-mail by John J. Romanelli (which has been uploaded by DPI into the View Permit system under Engineering) titled: "Building Permit Plan, Assessors Map 134 Lot 123 Almy Street, New Bedford, Massachusetts", having a date of 3/26/2020 (last revised date of 10/5/2020), as prepared by Zenith Consulting Engineers, LLC and stamped/signed by Jamie L. Bissonnette, P.E. (Civil), was approved as the "final" site plan and conditionally approved by DPI, as follows:
- a. Compliance with the City of New Bedford Stormwater Rules & Regulations/Ordinances is required for all project sites, regardless of size. All sites must implement sediment and erosion control measures and will be subject to the required construction site and sediment control inspections. Any project that involves disturbing 1 or more acres will require an EPA NPDES Construction General Permit (refer to Section 3.1.C of the Stormwater Rules & Regulations).
- b. The applicant is responsible for ensuring that Inspectional Services is provided with the "final" site plan (or any modifications approved by DPI thereafter) to be placed on file in the View Permit system.

2.) Must provide 1 stamped/signed copies of the "final" site plan approved by DPI for each of the permits being sought (i.e. water, sewer/drain and sidewalk/driveway permits) for the proposed structure. In addition, a copy of the foundation permit and of the stamped/signed foundation as-built plan must also be submitted.

Please Note: Any representative pulling permits on behalf of the owner must provide DPI with a permission slip. If the property was acquired within the past 6 months, then a copy of the recorded deed showing property ownership must also be provided.

3.) Must contact DPI-Engineering to measure for an address number once the front door is framed. The CO will not be signed unless the legal address issued by the City is permanently affixed to, above, or next to, the main door entrance to which it was assigned such that it is highly visible from the street.

Please be advised that any and all future modifications to the site plan that was reviewed/approved for the above project and placed on file at DPI as the "final" site plan must be resubmitted for review/approval if said changes entail work that falls under the jurisdiction of DPI.

Note to Inspectional Services:

Please kindly print the DPI comments for the applicant at the time they pick up their foundation permit. It is imperative that the applicants receive these comments when they are issued the foundation permit so that they are aware of the conditions under which it was approved.

HAWTHORNE PROPERTY MANAGEMENT LLC 5 CAUSEWAY RD FAIRHAVEN, MA 02719-2237	DATE	2709 53-447/113 451 CHECK ARMOR
PAY TO THE CITY OF NEW BEDFORD FIVE HUNDRED ROCKLAND TRUST		\$ 500 . DOLLARS Photo Safe Deposite Details on back
FOR WATER PORUIT	0055411	


and the

22

were "

Not a valid permit until processed by DPI - 05.11.2021 - AJ approved processed Af NEW BEDFORD WATER WORKS SERVICE 34125 APPLICATION FOR SERVICE NEW BEDFORD 05. B. 2021 40 05.13. 2021 Sewer 24936 I HEREBY ACKNOWLEDGE the receipt of a copy of the Regulations prescribed in the Ordinance of the City, for the use of Water, and I request that the water may be furnished through a meter at Almy St (SS) 240' W x Acustret Aue 134 Jot 123 at such rates as may from time to time be established by the City. I hereby agree to pay promptly the bill for the Service pipe laid down for my premises, and to pay all dues for water, and I agree to conform to the said Regulations and to all provisions of the Water Ordinances, until written notice is given by me or my agent to cut off the supply. Arronio Martinto 90 Bridge St. Faishaver MA Single family TELEPHONE 714-263-1105 Service laid RJ Caressa Size and kind of pipe 1 Copper From 8" main (CA) on Almy & si Turned on Location Reading Paid Paid Check 2709

31-727



ALMY STREET

NEW BEDFORD, MA

I CERTIFY THAT THE FOUNDATION SHOWN HEREON, AS BUILT, CONFORMS TO THE CITY OF NEW BEDFORD ZONING SETBACK REQUIREMENTS.

PROFESSIONAL LAND SURVEYOR DATE

DATE: APRIL 6, 2021

SCALE: 1"= 20'



ZENITH LAND SURVEYORS, LLC 1162 ROCKDALE AVENUE NEW BEDFORD, MA 02740 (508) 995-0100

